TUMKUR DIVISION.

Notification dated 14th November 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M. of 9th December 1930, for improving and extending the Mahadwara and Chandrasala and repairing Santanakeswara temple at Jain Basthi at Nittur, Gubbi Taluk, Tumkur District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for improving and exteining the Mahadwara and Chandrasale and repairing Shantanakeswara temple at Jain Basthi" at Nittur, Gubbi Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Tumkur, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual bond in default of which his tender will be cancelled and earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lumpsum provisions are subject to modifications as per data worked out during execution. For individual items of work under lumpsum provisions, the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

13. Masonry includes bond slabs to be introduced at an interval of 2 feet.

Abstract estimate for improving and extending the Mahadwara and Chandrasala and repairing Shanthanakeswaraswamy temple at Jain Basthi at Nittur, Gubbi Taluk :—

Sl. No.	Items of work	Unit	Rate in words	Rate in figures	Quantity	Cost
	1. *Repairs to Santhanakeswaraswamy temple.*			Rs. a. p.		
1	Earthwork excavation foundation ...	C.yd.			65	
2	Jelly concrete in chunam mortar ...	C.ft.			227	
2a	Stone in clay for foundation ...	,,			212	
3	Burnt stone in chunam mortar :— Bond slabs have to be introduced at the interval of two feet.	,,			1,452	
4	Cement pointing	Sqr.			40·02	
5	Burnt stone in mud :—Bond slabs have to be introduced at interval of two feet.	C.ft.			212	
6	Pointing with chunam mortar ..	Sqr.			12·96	
7	Burnt brick in chunam mortar ...	C.ft.			536	
8	Ornamental coping over garbhagudi ...	R.ft.			7	
9	Plastering with chunam mortar ...	Sqr.			20·50	
10	Scraping the old plastering ...	,,			12·08	
11	Jelly concrete grouting in chunam mortar.	Lump			sum	

Sl. No.	Items of work	Unit	Rate in words	Rate in figures	Quantity	Cost
				Rs. a. p.		
12	Rounding off corners at the junction of parapets in the roofing.	R.ft.			190	
13	Applying carbolastic to the cracks of the terrace.	Lump			sum	
14	Removing the roots of green plants on the roofing by applying Atlas weed killer.	Lump			sum	
15	Repairing the images of lines at corners	Lump			sum	
16	Rough stone pitching 3 miles lead ...	C.yd.			69	
	Improving and extending the Chandrasala.					
1	Dismantling the side walls, lowering the roof slabs and removing steps and pillars.	Lump			sum	
2	Earthwork excavation ...	C.yd.			26	
3	Jelly concrete in chunam mortar ...	C.ft.			560	
4	Burnt stone in chunam mortar with bond slabs at an interval of 2'.	"			889	
5	Ornamental brick parapets 2½ feet high with plastering.	R.ft.			65½	
6	Burnt stone slabs 6" to be roughly dressed set in mortar.	S.ft.			333	
7	Burnt stone slabs 6" dressed new ...	"			848	
8	Cut stone pillars with bases and capitals	C.ft.			57	
9	Cut stone beams	"			93	
10	Plastering with chunam mortar ...	Sqr.			4·50	
11	Pointing with cement	"			16·87	
	Improving and extending Mahadwaram.					
1	Dismantling the present mud walls removing old slabs and using them to Chandrasala.	Lump			sum	
2	Earthwork excavation	C.yd.			18	
3	Jelly concrete in chunam mortar ...	C.ft.			357	
4	Burnt stone in chunam mortar with bond slabs at an interval of 2 feet.	C.ft.			977	
5	Ornamental brick parapet 2½ feet high with plastering.	R.ft.			64	
6	Burnt stone slabs 6" thick dressed ..	S.ft.			676	
7	Cut stone pillars with bases and capitals	C.ft.			22½	
8	Cut stone beams	"			50	
9	Teakwood door shutters 3" thick straps and hinges, etc., complete with chacolate painting.	S.ft.			34	
10	Plastering with chunam mortar ...	Sqr.			2·40	
11	Pointing with cement	"			13·08	
12	Extending the compound wall by the side of Mahadwara and unforseen charges.	Lump			sum	

A. TANDONI RAO,
Executive Engineer.

MYSORE DIVISION, MYSORE.

Dated 21st November 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 15th December 1930, for constructing two additional rooms in the Taluk Cutchery at Malvalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1931.